
# The Scintillator Upgrade of IceTop

# **Performance of the Surface Array**



ICRC 2019 – July 26 Madison, Wisconsin, USA Matt Kauer – for the IceCube Collaboration







### **Motivation**

 IceTop is accumulating about 20cm of snow a year and the energy threshold is increasing

 We need a cost effective and robust IceTop upgrade to push the energy threshold back down and do more cosmic ray physics

 Also a proof of design of the infrastructure in development for the IceCube Upgrade






See D. Tosi's talk up next...


Matt Kauer

X (m) ICRC 2019 - July 26

### **Scintillator Panel Design**


- 16 scintillator bars extruded by FNAL, 1cm x 5cm x 1.875m (area = 1.5 m<sup>2</sup>)
- 16 Kuraray Y11(300) wavelength shifting fibers looped through 2.5mm holes in the scintillator
- 32 fiber ends read out by 6x6 mm<sup>2</sup> Hamamatsu 13360-6025PE (25um pitch)
- On-board electronics (voltage control, temperature sensor readout, data transfer)







On-board Electronics



Surface Field Hub

### The DAQs

#### Two different DAQ concepts tested

#### microDAQ

- 3 gain channels operating simultaneously
- Waveforms are charge integrated and charge plus timestamp digitally transferred to the surface field hub
- SiPM gain is temperature compensated via bias voltage control from the microDAQ firmware



#### **Analog Readout Module**

- 2 selectable gain channels
- Waveforms transferred analog to the surface field hub (SFH)
- Timestamps provided by the SFH
- SiPM gain is temperature compensated via bias voltage in SFH firmware




Hybrid-DAQ in development for the IceTop Upgrade


Combine the best attributes of both...

### **Surface Field Hubs**

Proof of concept for the IceCube Upgrade

- Timing and Coms via WR-LEN fiber
- Power via copper






- Timing transferred via copper from the SFH to the scint panel
- Coincident events with IceTop are ~330ns offset due to 70m of copper cable delay between the SFH and the scint.


### Characterization

Measure the gain and light yield of the scint panels in-situ


Measure the gain using PE peak separation from Gaussian fits

Much quicker and more robust method is to take the FFT of the finger spectrum






Measure the light yield from the scint panel by fitting the minimally ionizing particle (MIP) peak




### **Optical Simulations**


- Exhaustive Geant4.10 optical simulations return 40-45 PE/MIP
- Consistent with measurements




See A. Leszczynska and M. Plum's poster (PS1-190) Great Hall, 4th floor, after this session





### **Temperature Compensation and Stability**



- Fit the temp-volt-gain plane
- Use the fit constants for the temp compensation
- Currently set to a gain of 30 ADC/PE to optimize the dynamic range of the DAQ









## **Prototype Deployment**


- Deployed Jan 2018
- 3 scint pairs over/near IceTop stations
- Surface field hubs at the center of the array




### **Prototype Array Performance**


- Reconstructed showers coincident with IceTop
- Resolution limited by small size of the Scint array













ICRC 2019 - July 26

# **Scintillator Upgrade Simulations**


- IceTop Upgrade plans for 32 stations with 8 scintillator panels at each station
- Iron induced shower threshold ~250 TeV
- Proton induced shower threshold ~200 TeV


#### Threshold Improvement





See A. Leszczynska and M. Plum's poster (PS1-190) Great Hall, 4th floor, after this session







#### **Radio Extension**

 IceTop Upgrade plans for 32 stations with 3 antennas at each station

3 scint to trigger radio

Energy range 0.2 PeV – 1.0 EeV





See F.G. Schroeder's poster (PS1-210)
Great Hall, 4th floor, after this session
And M. Renschler's poster (PS3-207)
Great Hall, 4th floor, Tuesday afternoon

### **Summary**

- Two successful prototype arrays operating since 2018
- Scintillator arrays are well characterized and stable
- Successful proof of design of the surface field hub towards the IceCube Upgrade
- Shower reconstructions are consistent with IceTop
- IceTop Upgrade simulations demonstrate significant improvements for cosmic ray science
- Refurbished prototype station to be deployed January 2020

